

ADDENDUM NO. 1

GREENVILLE CITY SCHOOLS Memorial Hall Masonry Repairs ó Phase I Temporary Shoring

July 14, 2010

To: Planholders

From: Mote & Associates, Inc.
214 West Fourth Street
Greenville, Ohio 45331
Phone: (937) 548-7511
Fax: (937) 548-7484
E-mail: info@moteassociates.com

Re: Greenville City Schools
Memorial Hall Masonry Repairs ó Phase I Temporary Shoring

This addendum forms a part of the Contract Documents and modifies the original Contract Documents dated May 2010. Acknowledge receipt of this Addendum in space provided on the Bid Proposal form. Failure to do so may subject the Bidder to disqualification.

1. The landscaping shall be removed and then replanted in the same location upon placement of the proposed footings.
2. The top elevation of the concrete pilasters in the landscaping areas shall be set 6ö below finished grade and the top elevation of the concrete pilasters in the concrete landing shall be set 4ö below finished grade.
3. There shall be 4ö of jack space, with threaded bolt, between the base plate of the columns and the top of the concrete pilasters.

End of Addendum