

ADDENDUM NO. 1

VILLAGE OF ARCANUM Sanitary Sewer Separation – Phase III Albright Street Reconstruction

June 15, 2010

To: Planholders

From: Mote & Associates, Inc.
214 West Fourth Street
Greenville, Ohio 45331
Phone: (937) 548-7511
Fax: (937) 548-7484
E-mail: info@moteassociates.com

Re: Village of Arcanum – Sanitary Sewer Separation – Phase III
Albright Street Reconstruction

This addendum forms a part of the Contract Documents and modifies the original Contract Documents dated May 2010. Acknowledge receipt of this Addendum in space provided on the Bid Proposal form. Failure to do so may subject the Bidder to disqualification.

1. Page 10 of the Plans and the Bid Proposal Form (Section 00 41 43) in the Contract Documents shows 430 lineal feet of 4" conduit type "B" (707.32). The ODOT specification number was listed incorrectly and should be ODOT 707.31 instead of ODOT 707.32.
2. On Page 5 of the Plans it states "Water Test Note: The Village of Arcanum shall be responsible for all costs associated with the water tests needed for this project." The following is a clarification for this note:
 - a. This note only refers to the lab test required to check for total coliform bacteria. The pressure test and all additional water tests required per the Contract Documents, Specifications and Plans shall be solely the responsibility of the contractor.
 - b. The contractor is responsible to chlorinate and flush the system.
 - c. The Village will take two consecutive (at least 24 hours apart) total coliform samples, transport these samples to an OEPA approved lab and pay for the lab fees for these two samples.
 - d. If the first two total coliform samples do not test "negative for total coliform", the contractor is responsible to follow the testing requirements of the Contract Specifications until two consecutive samples test "negative". All samples will be taken by the Village of Arcanum and sent to an OEPA approved lab of their choice. However, any time spent and any cost incurred by the Village for water samples needed after the first two samples will be charged to the contractor.
3. The four existing storm catch basins at the intersection of Albright Street and Second Street shown on Page 10 of the Plans are to be carefully removed and delivered to the Arcanum Street Department building (302 South Albright Street) for future use by the Village.

End of Addendum