

# **ADDENDUM NO. 1**

## **NORTHEAST STORM SEWER IMPROVEMENTS**

**Potsdam, Ohio**

**JULY 2, 2009**

To: Planholders

From: Mote & Associates, Inc.  
214 West Fourth Street  
Greenville, Ohio 45331  
Phone: (937) 548-7511  
Fax: (937) 548-7484  
E-mail: info@moteassociates.com

Re: Northeast Storm Sewer Improvements Project

This addendum forms a part of the Contract Documents and modifies the original Contract Documents dated June 2009. Acknowledge receipt of this Addendum in space provided on the Bid Proposal form. Failure to do so may subject the Bidder to disqualification.

1. The proposed storm sewer in the cultivated fields (from the proposed headwall on sheet 4/8 to CB#2 on sheet 6/8) shall be perforated dual walled HDPE pipe.
2. Horses are pastured on the Croley property shown on sheet 6/8. It will be necessary for the contractor to provide temporary fencing to keep the horses confined to the west of the proposed construction for a period of time needed to construct the sewer through the property. When the installation is completed, the contractor will need to maintain temporary fence to keep the horses off the seeded area until grass is established. However, they shall be permitted to access the east end of the pasture field by allowing a pass over the new storm sewer. After the grass is established, the temporary fence can be removed and remain the property of the contractor. All permanent farm fence required to be removed for the construction shall be re-erected to provide a rigid, taut fence. The fence fabric shall be stretched and securely fastened to the line posts using galvanized ties. Use one tie at the top and bottom horizontal wires and one tie for each alternate horizontal wire below the top wire. All costs associated with fence replacement and temporary fence erection and removal shall be included in the price bid for item 201, Clearing and Grubbing.

3. All existing grassed areas shall be seeded and mulched using the seed mixture indicated under note # 6 on sheet 2/8. The pasture fields shall be seeded and mulched with the following mixture at a rate of 20 lbs. per acre:

- 45% Orchard Grass
- 20% Kentucky Bluegrass
- 15% Timothy
- 15% Fawn Fescue
- 5% Alfalfa

All costs associated with seeding and mulching shall be included with the cost of the pertinent piping installed through the area.

4. This addendum will be posted on our website. Please see the following link:  
<http://www.moteassociates.com/projects.htm>.

END OF ADDENDUM